



TEST REPORT

TEST OF A NON CATALYTIC SINGLE BURN RATE WOOD STOVE FOR EMISSIONS AND EFFICIENCY

PER EPA Method 28R, ASTM E2515 and ASTM E2780, MAY 2015

Client: Wolf Steel
Model tested: Napoleon NZ 3000H

Attention: Rafaël Sanchez

TESTED BY:

Services Polytests
695-B Gaudette
St-jean-sur-Richelieu, QC, J3B 7S7

TEST DATES:

REPORT DATE: November 20th 2015

Project number: PI-20116

All services undertaken are subject to the following general policy: Reports are submitted for exclusive use of the clients to whom they are addressed. Their significance is subject to the adequacy and representative character of the samples and to the comprehensiveness of the tests, examinations or surveys made. This document may not be reproduced except in its entirety without the written permission from Services Polytests. Services Polytests have not been involved in any R&D design consulting regarding this unit as requested by the NSPS.

Tested:

written by:



Danick power P. Eng & Maxime Martin



Danick Power, P. Eng

Verified (Third party certifier):

Intertek Representative



Claude Pelland, Eng.
Intertek Project Engineer

1 INTRODUCTION

1.1 GENERAL

Laboratory

- Location: Services Inc., 695-B Gaudette St-jean-sur-Richelieu QC, Canada J3B 7S7
- Elevation: 100 feet above sea level

Test program

- Purpose: unit qualification NSPS 2015 wood stove (emission limit 4.5gr/hr)
- Test dates: November 9th to 12th 2015
- Test methods used:
 - Particulate emissions: ASTM E2780 ; ASTM E2515 methods 28R and ASTM E2515 as referred into 40 CFR Part 60 Subpart AAA
 - CO emission & Efficiency: CSA B415.1-10

1.2 TEST UNIT INFORMATION

General

- Manufacturer: Wolf Steel
- Product type: Hybrid Catalytic freestanding single burn rate wood fireplace
- Combustion system: Hybrid Catalytic Wood fireplace
- Unit tested: NZ 3000H
- Vent : 7 inch single wall pipe

Particularities

- Options: Blower fan
- Product line similarities: na

1.3 RESULTS

Emission results obtained

- Average emission rate: 3.25 grams/hour
- Maximum rate cap: 4.6 grams/hour at run 3

Conformity: NSPS Phase 2015

1.4 PRETEST INFORMATION

Unit condition: The unit was received by carrier in July 2015. The 48hrs of aging is made in months of August to October 2015 during preliminary testing.

Set up

- Venting system type: 7 inch steel pipe and insulated chimney
- System height from floor: 15 feet
- Particularities: none

Break in period

- Duration: the unit was received from the manufacturer and run for at least 48 hours at a category 2 burn rate with adequate documentation of fuel additions and flue and unit temperatures during the months of August to October 2015.
- Fuel: Crib wood

2 SUMMARY OF TEST RESULTS

2.1 EMISSIONS

Run Number	Test Date	Burn Rate (kg/hr)	Emission Rate (g/hr)	Heating Efficiency (%) Overall)	1st hour Emission Rate (g/hr)	CSA B415.1 CO emission Gr/hr
1	9-11-2015	1,942	3,21	63,4%	6.32	48
2	10-11-2015	1,266	2,15	62,7%	8.05	24.6
3	11-11-2015	1,108	4,56	62,1%	14.1	32
4	12-11-2015	0,731	3,24	67,2%	10.26	38

2.2 AVERAGE CALCULATION

Test No.	Burn Rate	(E) Ave. Emission Rate g/hr	(OHE) %	Heat Output (BTU/HR)	Prob	Weighting Factor
4	0,73	3,200	67,16	9200	0,1710	0,4660
3	1,11	4,600	59,60	12200	0,4660	0,4106
2	1,26	2,100	62,07	12700	0,5816	0,4378
1	1,94	3,200	63,40	22400	0,9038	0,4184
Average		3.25	63.17			

Average Emissions Rate: 3.25 g/hr

Average Overall Efficiency: 63.17%

2.3 TEST FACILITY CONDITIONS

Run Number	Room Temperature		Barometric pressure		Relative humidity		Air Velocity	
	Before (F)	After (F)	Before (in.Hg)	After (in.Hg)	Before (%)	After (%)	Before (ft/min)	After (ft/min)
1	72	76	30,357	30,298	36,2	29,8	21	19
2	73	77	30,268	30,121	32,4	29,4	19	22
3	73	75	29,973	29,825	31,9	29	24	22
4	73	73	29,796	29,766	38,7	42,1	50	30

2.4 FUEL QUALITIES

Run Number	Pre-test Load			Test Load					
	Loading Weight Wet Basis (lbs)	Moisture Content Dry Basis (%)	Coal bed Weight (lbs)	Weight Wet Basis (lbs)	Density Wet Basis (lbs/cuft)	Moisture Content Dry Basis (%)	Piece Length (in.)	Number of 2X4's	Number of 4x4's
1	14,93	21,90	3,7	14,95	6,795	20,39	13,75	3	2
2	14,04	22,00	3,4	14,11	6,414	19,44	13,625	3	2
3	14,03	22,00	3,3	14,00	6,364	22,81	14	3	2
4	16,80	21,71	3,7	14,07	6,395	23,26	12,875	3	2

2.5 DILUTION TUNNEL FLOW RATE MEASUREMENTS AND SAMPLING DATA (ASTM E2515)

Average dilution tunnel measurements				Sample Data			
Run Number	Burn Rate (Min)	Volumetric Flow Rate (dscf/min)	Total Temperatures (°R)	Volume sampled (DSCF)		Particulate catch (mg)	
				1	2	1	2
1	174	300,67	563,89	30,613	29,543	5,50	5,20
2	254	278,71	558,42	44,854	43,145	6,00	5,30
3	280	284,21	556,73	49,079	47,171	13,30	12,60
4	425	313,54	548,55	75,330	72,849	13,50	12,10

2.6 DILUTION TUNNEL DUAL TRAIN PRECISION

Run Number	Sample Ratio		Total Emission (g)		
	Train 1	Train 2	Train 1	Train 2	% Deviation
1	1708,97	1770,86	9,40	9,21	1,03%
2	1578,28	1640,80	9,47	8,70	4,26%
3	1621,42	1686,99	21,42	21,15	0,65%
4	1768,98	1829,21	23,85	22,10	3,79%

2.7 GENERAL SUMMARY OF RESULTS

Run Number	Burn Rate (kg/hr)	Average Surface Temperature (F)	Change in surface Temperature (F)	Initial Draft (in. H ² O)	static pressure tunnel (in. H ² O)	Primary Air Setting	Run Time (min)
1	1,942	320,07	5,4	0,014	0,210	Fully open	174
2	1,266	390,53	-22,7	0,016	0,210	Fully closed	254
3	1,108	380,06	-12,3	0,065	0,220	Fully closed	280
4	0,731	-55,82	-55,8	0,000	0,210	Fully closed	425